

BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2020-21/OW/WORK_INDENT42421/CALL-3

APPROVED SCHEDULE - B

No.EE/BTP/BBMP/E-PMT/15/2020-21, Date: 29-03-2021

Name of Work:Improvements to footpath and roads in ward no 8 (Call-3)

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of	
				SHIVARAJU KUMARAKSHAY	
				In Figures	In Words
1	324.7	Providing and fixing pre cast solid cement concrete kerb stones made out of CC 1:2:4 with top and bottom width 114 and 165 mm respectively, 400mm high and 450mm in length finished with CM 1:3 plastering and finishing cutting including formwork, curing, including cost of materials, labour charges of machinery, loading and unloading, lead and lift, transportation etc.,complete. (P.No.25, I.No.5.30 of PW,P&IWTD S.R 2018-19)	No.	350.0	Rupees Three Hundred Fifty Only
2	4619	KSRRB 800-1. Painting two coats after filling the surface with synthetic enamel paint in approved shades on new plastered concrete surfaces, with materials, labour complete as per specifications. MORTH Chapter 8 (P.No.182, I.No. 24.1 of PW,P&IWTD SR 2016-17)	Sqm	70.0	Rupees Seventy Only
3	100.57	Providing and laying/fixing cement base, precast, pre polished cement concrete, designer tiles 25mm thick for flooring conforming to IS 1237 heavy duty tiles for flooring, treads of steps and landing, laid on a bed of 12mm thick cement mortar 1:3 mis finished with flush pointing using white cement, including cost of materials, including cutting, griding the edge to half/full round wherever required, labour, curing complete as per specification. (P.No. 109, I.No. 14.62 of PWD SR 2018-19)	Sqm	1130.0	Rupees One Thousand One Hundred Thirty Only

Kumar Aravind . S
Signature of the Contractor

Chandana
Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92
13/07